IN SITU DAMAGE EVALUATION OF GEOGRID USED IN ASPHALT CONCRETE PAVEMENT

C. Chazallon, T.C. Nguyen

ICUBE, UMR 7357 CNRS, INSA de Strasbourg, France

M. L. Nguyen, P. Hornych

IFSTTAR, Nantes, France

D. Doligez

6D Solutions, Sainte Foy Les Lyons, France

L. Brissaud, E. Godard

Colas S.A., Magny les Hameaux, France

ABSTRACT: In this paper we present the first results of the national French project SolDuGri dealing with pavement reinforcement by geogrids. In this project, full scale tests have been performed to evaluate the in situ damage of geogrids in asphalt concrete pavements. The tests consisted in building test sections with four different types of geogrids, and two different compacted asphalt concrete layers above. After construction, the geogrids have been recovered from different locations on the field sections, where they had been subjected to compaction only, or also to construction traffic, and their residual mechanical properties have been evaluated in the laboratory.

1 INTRODUCTION

Since the late 1960s, coated glass fibre grids also known as 'geogrids' are used as reinforcement materials in different pavement structures subjected to fatigue cracking. Geogrids are generally used for the rehabilitation of cracked pavements (semi-rigid pavements, asphalt pavements and flexible pavements), but nowadays they are also included in new pavements. To ensure an efficient reinforcement, and a reliable design of the pavement incorporating a grid, it is required to know the residual mechanical properties of the geogrid after its implementation and compaction of the above asphalt concrete layer and the level of damage of the grid. This paper presents the first results of the national French project SolDuGri dealing with pavement reinforcement by geogrids. In this project, full scale tests have been performed to evaluate the in situ damage of geogrids in asphalt concrete pavements. The tests consisted in building test sections with four different types of geogrids, and two different compacted asphalt concrete layers above. After construction, the geogrids have been recovered from different locations on the field sections, where they had been subjected to compaction only, or also to construction traffic, and their residual mechanical properties have been evaluated in the laboratory. We will present the materials used and the tested sections, then the tension tests on recovered grids.

2 MATERIALS USED

2.1 Semi coarse asphalt concrete material

For this test the asphalt concrete material chosen is a standard semi coarse asphalt concrete (SCAC) designed with the available aggregates in the area where the experimentation was to be carried out. This formula has been used in the traditional hot mix version and as a warm mix AC in order to study the effect of the temperature on the glass geogrid reinforcement.

The aggregates are from the gneiss quarry of Bréfauchet in Chéméré (Loire-Atlantique, France), they are 100 % crushed aggregates. This SCAC is an "AC 10 surf 35/50" according to EN 13108-1. It is constituted of a 0/2 mm sand and 2/6.3 mm and 6.3/10 mm coarse aggregates from Bréfauchet. A limestone filler is also included in the formula. The binder is a 35/50 penetration grade bitumen according to EN 12591. The formula has been designed to satisfy the specification of the French SCAC 0/10 class 3. The most relevant characteristics are the void content of 8.1 % at 60 gyrations of gyratory compactor test. The water sensitivity is 82.1 % at the Duriez test and the rut depth is 3.9 % at 30000 cycles (60°C).

Other characteristics have been measured: the stiffness modulus and the fatigue resistance of the

mix. They will be important for the following steps of the study. The stiffness modulus, measured by two points bending tests, is 12945 MPa at 15°C and 10Hz for the hot mix (160°C) and 12674 MPa in the same conditions for the warm mix (135°C). The fatigue test gives a failure strain of 109 microstrains for 1 million load cycles (at 10°C, 25 Hz) for the hot mix and 111 microstrains for the warm mix. Both fatigue and modulus tests indicate no significant difference between the two mixes

These asphalt concretes have been used in their usual range of thickness: 5 to 7 cm. The tack coat between the asphalt layers, including the grid impregnation, was a classical cationic rapid setting bitumen emulsion, classified as C69B3 according to EN 13808.

2.2 Glass fiber grids

Four different grids, made of glass fiber coated with two different resins, of different stiffness, were chosen for the study. The first two grids (G1 and G2) had a strength of 20 kN/m for a strain of 1%, and were coated with a soft resin and a stiff resin, respectively. The two other grids (G3 and G4) had a 40 kN/m strength, and different, soft and stiff resins.

3 TESTED SECTIONS

In total, five test sections were built for the SolDugri project on an existing subgrade with a load-bearing capacity higher than 100 MPa, measured at different positions by dynamic plate load test. One of these sections, 15 meters long, was devoted to the study of grid damage after construction. This section included the four different types of geogrids (G1, G3, G2 and G4).

A levelled asphalt concrete layer was firstly realized on the existing subgrade. Four SCAC layers, each 5 cm thick were then laid one after the other to constitute the pavement test section (figure 1).

The 20 cm thick pavement structure was chosen because a thick structure was required for other laboratory studies planned in the SolDuGri project, in particular tests for the characterization of the bond between the asphalt and geogrid layers, which required large specimens. Void content measurements by a Troxler device on the surface of the 2nd and 4th layers indicated mean void contents of 5.7 % and 5.8 % respectively on sections made of hot mix and 6.7 % and 7.1 % on the section made of warm mix.

The different geogrids were placed on the surface of the second SCAC layer. To study the effect of different surface conditions on the damage of the geogrids, on one half of the section, the surface of the second SCAC layer was milled, before placing the grids (to simulate the reinforcement of an old pavement – surface B), and the second part was com-

pacted normally, to simulate a new construction (surface A). On both parts, a tack coat with 500 g/m² of residual bitumen was applied, to ensure impregnation of the geogrids. A tack coat with 300 g/m² residual bitumen was applied on the other interfaces. The full scale test sections were built using standard roadworks equipment as used on real construction sites (figure 2).

Figure 1. Transverse profile of test sections.

Figure 2 : construction of the full scale test sections, and trafficking of construction equipment on the grids

For the study of the geogrid damage after construction, a specific procedure of placement of the geogrids was adopted. The four different types of grids were cut in small sections, 72cm x 72 cm large, and some of the yarns (either warp yarns or

filling yarns) were protected with thin aluminum foil, to avoid impregnation by the tack coat, at specified areas. This partial protection of the grids was necessary, in order to perform tension tests on the yarns, after retrieving the grids. Indeed, to ensure a good fixing of the yarns on the testing machine, it was necessary to keep their ends clean, without any tack coat.

After construction, when the pavement was completely cooled, the geogrids were recovered from different locations on the field sections, where they had been subjected to compaction only, or also to construction traffic, by the trucks and by the finisher. Care was taken to minimize the damage of the grids during recovery. Each grid section was located and sawed in a bloc of about 64×64 cm². Each block was then placed inside a large oven, and heated to 40 °C, for about 5 to 7 hours. Once the asphalt concrete block was heated enough, it was taken outside the oven, and the asphalt concrete layers were separated carefully, in order to recover the grid.

The recovered geogrid sections were finally marked, to identify their type and their location on the field section, and sent to the laboratory, for evaluation of their residual mechanical properties.

Although great care was taken for the recovering of the geogrid sections, 100% of the yarns could not be recovered properly without any damage, due to the strong bond between the geogrids and the asphalt concrete layers. Three different configurations were observed after separation of the asphalt concrete layers: i) the geogrid was bonded to the bottom surface of the upper layer; ii) the geogrid was bonded to the top surface of the lower layer; iii) the geogrid was bonded to both layers. Geogrids G1 and G3 generally adhered only to one asphalt concrete layer, often the upper layer, and they were easier to retrieve. On the other hand, grids G2 and G4 had a tendency to adhere to both layers due to the use of a different, softer, coating resin, and they were more difficult to extract. These observations have been considered for the laboratory evaluation of the residual mechanical properties of the geogrids, and after a visual examination, all the grids or yarns which seemed to have been torn or bent during the extraction were eliminated.

4 TENSION TESTS ON RECOVERED GRIDS

Only reclaimed grids with protected warp yarns have been tested till now, and the results are presented hereafter. Grids with protected filling yarns will be reclaimed in the next months and will be tested too.

In total, 32 grid sections were placed in the test section, and could be recovered; 7 have been tested till now. Each section was trafficked on more than 50% of its surface by the wheels or the caterpillars

of the finisher. This means that for the tension tests, slightly less than 50% of the yarns had been damaged only by the compaction, and a little more than 50% by both compaction and trafficking by the caterpillars or the wheels.

During recovery, the loading received by each grid was carefully identified (see table 1), and three different loading processes were distinguished :

- the grids submitted only to compaction of the upper layers, without any other loading (no loading -NL).
- The grids submitted to compaction and to loading by the wheels of the asphalt truck (tire -T).
- The grids submitted to compaction and loading by the finisher's caterpillars (cat). Due to the narrow asphalt layers, a small finisher with an overall width of the caterpillars of 1.5m was used. This width was smaller than the spacing of the truck wheels. Therefore, the zones loaded by the caterpillars were different from the zones loaded by the tires.

Table 1 : Number of warp yarns tested, per loading type

GRID	G1	G2	G3
No loading	33	10	7
Tires	41	24	25
Caterpillars	22		12

Each recovered grid was cut into individual warp yarns, which were submitted to tension tests. The yarn samples were 29 centimeters long, and were tested at 20°C. For each yarn, the mean elastic modulus was determined, by performing 3 load cycles, in the small strain range, between 100N and 400N for grids G1 and G2 , and between 100N and 1000N for grids G3. The strains were measured with a local extensometer. The same tests have also been performed on new grids, coming from the manufacturer, for comparison. The number of grid sections recovered from the pavement, for each type of layer surface condition (new layer (A) or milled layer (B)), and the corresponding number of yarns tested are indicated in table 2

Table 2: Reclaimed grids and yarns

GRIDS	G1	G2	G3
Surface layers and (number of reclaimed grids)	A (2) /B (1)	A (1) /B (1)	./B (2)
Number of warp yarns for tension tests	66/30	17/17	./44
Number of warp yarns for fatigue tests	./.	17/17	./19

(a)

(b)

(c)

Figure 3 : Residual tensile strength of warp yarns submitted to each type of loading, compared with Non-Loaded residual strength

Figure 3 compares the average residual tensile strength of each warp yarn type with the NL residual strength (considering all types of surface A/B together). Figure 3 shows that for the thinner grids (G1 and G2), the type of loading has an influence on the residual strength and that the grid which has the softer resin (G2) has relatively a higher residual strength than the stiffer one (G1). For the thicker grid (G3), the influence of the loading type is less evident; it seems, again, that the grid with the stiffer resin is more sensitive to the type of loading.

Figure 4 compares the average elastic modulus of each warp yarn type with the NL elastic modulus. The results show that the coefficient of variation is lower, and that the elastic modulus is less sensitive to the type of loading than the residual tensile strength (figure 3).

(a)

(b)

(c)

Figure 4 : Elastic modulus of warp yarns submitted to each type of loading, compared with Non-Loaded elastic modulus

Finally, figure 5 compares the average residual tensile strength after construction of each type of grid (considering all types of loading together), with the tensile strength of the new grids. In all cases, a huge loss of maximum tensile strength (between 60 and 80 %) is observed.

It is also found that with thinner grids, a milled pavement surface seems to cause less damage to the warp yarns than a new surface (results G1-A/B and G2-A/B on figure 5). This could be explained by the effect of the tack coat at the interface, which could preferentially fill the hollow grooves made by the milling, which are in the warp yarn direction. It can also be observed that grids with a softer resin have higher residual strengths, for each surface type, than those with a stiff resin.

For a thicker grid and stiffer resin (G3 compared with G1), one can observe that the residual strength is improved for the same surface type (B).

Figure 5: Average residual tensile strength of warp yarns after construction, compared to strength of new yarns.

All the yarns have been examined before testing. The main visible deteriorations of the yarns were punching (see figure 6). Sometimes, very small holes were also observed (figure 7), with or without cuts of the warp yarn (figure 8). Note that these deteriorations are not very easy to see on figures 6, 7 and 8, because the yarns are partially hidden by a non woven geotextile, attached to the grid.

Figure 6: Punching of a G3-B reclaimed warp yarn

Figure 7 : Hole on a G1-A reclaimed warp yarn

Figure 8 : Cut on a G1-A reclaimed warp yarn

Nevertheless we think that the main damage process is caused by the multiple indentation of the warp yarns by the aggregates during the compaction process of the hot mix asphalt. This is supported by the fact that the residual elastic modulus of the yarns recovered after construction is about 75% of the elastic modulus of the new yarns (see figure 9); this loss in modulus is relatively limited, compared with the loss in tensile strength. The residual tensile strength, is only about 22.5% of the strength of the new yarns, for grids G1 and G2.

Figure 9 : Residual elastic modulus of recovered warp yarns, compared to new yarns

Therefore, it seems that a loss of section occurs during the compaction process (of the order of 25% for thinner grids) and that the multiple indentations do not affect the elastic modulus, but give rise to stress concentrations initiating crack propagations and delamination in the warp yarns (as suggested by the failure patterns on figure 10) when tensile tests are performed.

(c)

(b)

(a)

Figure A :Warp yarn rupture : (a) intact grid G1, (b) recovered grid G1-A, showing delamination (c) recovered grid G3-B, showing delamination

5 DISCUSSION OF THE RESULTS

The results obtained on the different grids recovered after construction suggest that significant damage can occur in the pavement, during installation of the grids. For the pavement section studied in this project, the damage leads to a limited loss of elastic modulus (about 20 to 25 %), but to a much higher loss of tensile strength (60 to 80 %). The results are consistent, because the damage is more important for the thinner grids. It is also increased when the grids are subjected to loading by the construction equipment. It is also clear that the resin coating protects the glass fibers, and that its quality influences the level of damage.

The very high losses of tensile strength observed in this study raise some questions. They are higher than those observed in a similar study, (Gonzalez - Torre et al., 2014), which found a decrease of tensile strength of about 40 % for geogrids. This may be explained by several factors :

- first, the grids were subjected to severe loading, because of the low thickness of the upper asphalt concrete layers (5 cm). They were also submitted to the compaction process twice, because they were overlaid by two successive asphalt concrete layers
- It cannot be excluded that the recovery procedure created some additional damage, because, especially for grids G2 and G4, the bond with the asphalt layers was very good. Therefore, it was not possible to remove the grids without some pulling, which could have led to some deterioration. However, as mentioned previously, the

yarns apparently damaged by the extraction (showing some splitting or folding of the glass fibers) were removed.

At this stage, only 7 of the 32 grid sections installed in the pavement have been recovered, and additional tests will be performed on the remaining grids. For these additional tests, attempts will be made to improve the extraction procedure. In particular, a higher temperature could be used to facilitate the recovery of the grids.

Finally, the significance of the loss of tensile strength of the grids needs to be discussed. In a pavement, the grids work at low strain levels, certainly lower than 1 %, and at such low strain levels, their maximum tensile strength will never be attained. Thus, in a pavement, the most important mechanical property is the elastic modulus of the grids at low strain levels, and not their failure strength. And the tests have shown that the loss of elastic modulus, due to installation damage, is limited (20 to 25 %) Thus, even if the tensile strength of the grids is significantly reduced, their efficiency as a reinforcement may still be sufficient.

6 CONCLUSION

During their installation in a pavement, geogrids can suffer from physical damage due to mechanical and thermal loads. Currently, this damage is not quantified, and not taken into account in design. In the project Soldugri, a study has been performed to study this installation damage. Four different geogrids have been placed in a pavement, and then recovered, and submitted to modulus and tensile strength tests.

The first results show that the damage during installation of the 4 geogrids reduced significantly the tensile strength, but did not alter too much the E modulus at small strain level. These results also indicated that the level of damage depends on the thickness of the grids, and also on the type of resin coating protecting the yarns.

It is planned to continue these studies, to confirm the first results, to understand better the parameters influencing the installation damage, like the type of asphalt material, installation temperature, energy of compaction, construction traffic, and to improve the resistance of fiberglass grids to such damage.

7 ACKNOWLEDGEMENT

The work presented in this paper was sponsored by the French National Research Agency (ANR - SolDuGri project ANR-14-CE22-0019).

8 REFERENCES

M. Gharbi M.L. Nguyen, S. Trichet, A. Chabot (2017). « Characterisation of the bond between an asphalt layer and glass grid layers with help of a Wedge Splitting Test ». BCRRA 2017, Athenes.

I. Gonzalez-Torre, M. A. Calzada-Perez, A. Vega-Zamanillo and D. Castro-Fresno,(2014). Damage evaluation during installation of geosynthetics used in asphalt pavements, Geosynthetics international, 3, 21, 6

NF EN 12591 Décembre 2009, Bitumes et liants bitumineux - Spécifications des bitumes routiers

NF EN 13108-1 Février 2007, Mélanges bitumineux - Spécifications des matériaux - Partie 1 : enrobés bitumineux

NF EN 13808 Août 2013, Bitumes et liants bitumineux - Cadre de spécifications pour les émulsions cationiques de liants bitumineux